
# Status of the Pbar Source

Dave McGinnis
DOE Review
October 28, 2002

#### Overview

- The present pbar production rate which is at 66% of the design value is adequate to support present Run II operations.
- Before July of 2002, the horizontal emittance of a typical 100E+10 antiproton stack was about a factor of 2 larger than the Run II handbook design value.
  - $\Box$  At a stack of 100E+10 pbars the normalized horizontal transverse emittance was about 17 π-mm-mrad.
  - $\square$  The Run II handbook specifies 8  $\pi$ -mm-mrad at 100E+10 pbars
- During the period of Nov. 2001 through July 2002, almost 100% of the manpower and machine study time of the Pbar Source department was devoted to trying to reduce the horizontal emittance.
- We believe that the horizontal emittance growth was caused by
  - ☐ Intra-beam scattering (60%)
  - ☐ Trapped ions (40%)
- The intra-beam scattering (IBS) heating of the beam is worse now for Run II than it was in Run I because of the changes in beta functions that were the result of the Accumulator Lattice Upgrade

#### Transverse Emittance



# Accumulator Run II "Upgrades"

(why did we change the Accumulator Lattice)


- Main Injector Project was to increase the antiproton flux into the Accumulator by a factor of 2.7
  - ☐ A factor of 1.7 increase in the number of protons on target
  - ☐ A factor of 1.6 increase in 120 GeV proton production rate

$$\Phi = \frac{W^2 \eta E_d}{f_0 p \ln(\frac{F_{\text{min}}}{F_{\text{max}}})}$$

Antiproton flux though the Accumulator Stacktail Momentum Stochastic Cooling system

- Bandwidth W to increase from 1-2 GHz to 2-4 GHz
  - ☐ 15 meters of new Stacktail Pickup Arrays in A60
  - ☐ 15 meters of new Stacktail Kicker Arrays in A30
- Changed Accumulator lattice to keep Stacktail system stable
  - ☐ Schottky bands must not overlap in the Stacktail frequency range
    - ➤ Maximum frequency of the Stacktail system increased from 2 GHz to 4 GHz
    - > η must decrease from the Run I value of 0.022 to 0.012 in Run II
    - $\triangleright \gamma_t$  must increase from the Run I value of 5.5 to 6.55 in Run II


## Accumulator Lattice Upgrade



- $\gamma_t$  increase was obtained by adding negative dispersion at the "B7" bends
- Shunts were added to 6 of the 14 quads in each of six sectors
- The quads on either side of each of the high dispersion straight sections were increased in strength

# Intra-beam Scattering

• In the beam frame, if the longitudinal momentum spread is much less than the transverse momentum spread, the IBS formulas can be significantly simplified



#### Transverse IBS Growth Rate

- The heating of the longitudinal degree of freedom causes cooling for both transverse degrees of freedom.
- Additional mechanism heats the horizontal degree of freedom
  - At regions with non-zero dispersion, changes in the longitudinal momentum change the particles reference orbits, which additionally excites the horizontal betatron motion

$$\frac{d\varepsilon_x}{dt} = \frac{1}{2} \left\langle A_x \frac{d\theta_{\parallel}^2}{dt} \right\rangle \qquad \text{where} \qquad A_x = \frac{D^2 + (D'\beta_x + \alpha_x D)^2}{\beta_x}$$


Coefficient ½ is related to the fact that the beam is unbunched

• Finally, one can write for the emittance growth rates

$$\frac{d\varepsilon_{x,y}}{dt} = \frac{\sqrt{2\pi}e^4 NL_C}{8m_p^2 c^3 \gamma^3 \beta^3 C} \left\langle \frac{1}{\sigma_x \sigma_y \sqrt{\theta_x^2 + \theta_y^2}} \begin{bmatrix} 2A_x \Xi_{\parallel} (\theta_x, \theta_y) - \frac{\beta_x}{\gamma^2} \Xi_{\perp} (\theta_x, \theta_y) \\ -\frac{\beta_y}{\gamma^2} \Xi_{\perp} (\theta_y, \theta_x) \end{bmatrix} \right\rangle_s$$


where 
$$\Xi_{\perp}(x,y) \approx 1 + \frac{2\sqrt{2}}{\pi} \ln \left( \frac{\sqrt{3x^2 + y^2}}{2y^2} x \right) + \frac{0.5429 \ln(y/x)}{\sqrt{1 + \ln^2(y/x)}}$$

#### Run I and Run II Accumulator Lattices



- Both lattices are not designed to have small IBS
- Run II lattice amplifies IBS by more than factor of two in comparison with the Run I lattice.





#### Plan for Emittance Control

- We developed a two-fold plan to reduce the transverse emittance:
  - ☐ Better transverse stochastic cooling of the Accumulator core.
    - ➤ The bandwidth was increased by a factor of 2
    - > The center frequency of the band was increased by a factor of 1.5
  - ☐ Dual lattice operation mode of the Accumulator
    - $\triangleright$  Keep the "fast stacking" lattice ( $\eta$ =0.012) for pbar production
    - $\triangleright$  During shot setup, ramp the lattice with the beam at the core orbit to the "IBS" lattice ( $\eta$ =0.022)
      - The "shot" lattice will reduce the intra-beam scattering heating by a factor of 2.5
      - The "shot" lattice will increase the cooling rate by a factor of two increase in mixing due to the change in  $\eta$

$$\frac{\mathrm{d}\varepsilon}{\mathrm{d}t} \approx -\frac{\varepsilon}{\tau_{\mathrm{cool}}} + \frac{\mathrm{Heat}}{\varepsilon_{\mathrm{new}}^{3/2}} \qquad \frac{\varepsilon_{\mathrm{old}}}{\varepsilon_{\mathrm{new}}} = \left(\frac{\tau_{\mathrm{cool}_{\mathrm{old}}}}{\tau_{\mathrm{cool}_{\mathrm{new}}}} + \frac{\mathrm{Heat}_{\mathrm{old}}}{\mathrm{Heat}_{\mathrm{new}}}\right)^{2/5} = \left(2 \times 1.5 \times 2\right)^{2/5} \times \left(\frac{0.4 + 0.6}{0.4 + \frac{0.6}{2.5}}\right)^{2/5} = 2.4$$
Bandwidth

Better


Mixing

Reduced

IBS


## Accumulator Core Cooling Upgrade

- Initial Run II system consisted of a 2-4 GHz band and a 4-6 GHz band
  - The 2-4 GHz band is ineffective because of the small value of η
  - ☐ The 4-6 GHz band suffers from poor signal to noise.
- Replaced both core bands with a 3 band Debuncher style system
  - Better sensitivity
  - $\square$  More bandwidth (2x)
  - $\Box$  Better mixing factor (1.5x)



#### Slow Wave Structures

- The core cooling upgrade consists of slow-wave structures
- When the beam pipe can support a microwave mode (> 5 GHz in the Accumulator), binary combiner boards become ineffective
- The beam pipe of a slow-wave structure is designed to be above cutoff
- The slots of a slow-wave structure slow the phase velocity of the waveguide to match the beam velocity




# Core Cooling Arrays



- Project was started 10/30/01 and completed 6/15/02 (7.5 months)
  - ☐ 6 new cooling systems
  - ☐ 4 new ultrahigh vacuum tanks
- The effective cooling rate of the new system is 1.4x faster than the combined rate of the old systems

## Core Cooling Tank




- With full system equalizers the new system will be 2.5x faster than the combined rate of the old systems
- With an 82 mA stack, we have a peak signal to noise ratio of 8 dB at 7.5 GHz for a 7 pi normalized emittance

#### Accumulator "Shot" Lattice


- An Accumulator lattice with a much smaller IBS heating term was designed.
- The lattice was designed with the following constraints
  - □ No hardware changes to the present quadrupole configuration.
  - ☐ Same betatron tunes as the present Run II lattice
  - ☐ Zero dispersion in the odd straight sectors
  - ☐ High dispersion in the even straight sectors
  - ☐ Correct betatron cooling phase advances
  - ☐ Correct kicker phase advances
  - $\square$   $\gamma_{t} < 5.5 (\eta < 0.022)$
- Ramp Development began 4/9/02 and dual lattice mode became operational 7/17/02
  - ☐ Ramps are 100% efficient
  - ☐ Tunes are controlled to within 0.0005
  - ☐ Orbits are controlled to within +/- 1mm
  - ☐ Ramping from the Stacking Lattice to the Shot Lattice adds about 15 minutes to shot setup.

# Accumulator Lattice IBS Heating Term



#### Antiproton Source Emittances


Stack size vs. average core emittance
Before and after cooling upgrade, with shot lattice



#### Antiproton Source Short-Term Goals

- With antiproton source emittances under control, the focus of the Antiproton Source Department has shifted to increasing the stacking rate.
- We have achieved
  - ☐ an initial stacking rate of 12.4 mA/hr
  - $\square$  An average a production efficiency greater than 15x10<sup>-6</sup> pbars/proton
  - ☐ An initial production interval of 2.2 seconds
  - ☐ A stack of 160 mA in a 20 hr period.
- Our immediate goal is to achieve the initial Run II design goal of 18.5x10<sup>10</sup> pbars/hour with no stack
  - □ Production efficiency =  $16x10^{-6}$  pbars/proton on target
  - ☐ Initial production interval of 1.5 seconds
  - ☐ Be able to stack to a 200 mA stack in a 20 hr period.
    - > Stack at 16 mA/hr for a stack size of 50 mA
    - > Stack at 13 mA/hr for a stack size of 100 mA
    - > Stack at 9 mA/hr for a stack size of 150 mA
  - Be able to shoot from a 200 mA stack with emittances below 10pi (normalized)


# Present Pbar Stacking Performance




 We can achieve our stacking goals if we can reduce the initial production cycle time from the present 2.2 seconds to the design 1.5 seconds

## Why is the Cycle Time so Slow?

#### Accumulator Longitudinal Spectrum



#### Debuncher Momentum Spread vs. Cycle Time



- Beam must be cleared off the Stacktail deposition orbit before next beam pulse.
  - ☐ The more gain the Stacktail has, the faster the pulse will move.
  - ☐ The Stacktail gain is limited by system instabilities between the core beam and the injected beam
- For a given Stacktail gain, the larger the momentum spread of the injected pulse, the longer it takes to clear the pulse from the Stacktail Deposition orbit.
  - ☐ The momentum spread coming from the Debuncher is too large.

# Stacking Projects

- Debuncher Momentum Cooling Improvements
  - ☐ Smaller momentum spread delivered to Accumulator, which would permit faster cycle time. Faster cycle time would increase stacking rate at low and high stacks
- Transverse Debuncher Notch Filters for Bands 1 & 2
  - ☐ Removal of longitudinal lines would permit for larger transverse cooling gain which would permit faster stacking cycle times.
- Commission Core Momentum-Stacktail Compensation Legs
  - ☐ Keep the stacktail stable at high stacks. Stacktail gain could be increased. Faster stacking at large stacks would result.
- Implement Core Momentum "Spreading" during stacking
  - ☐ Keep the stacktail stable at high stacks. Stacktail gain could be increased. Faster stacking at large stacks would result.
- Stacktail Notch Filter Upgrade
  - ☐ Increasing bandwidth of the stacktail will permit faster stacking rates
- Develop Improved Transverse Compensation of the Stacktail
  - ☐ Reduce heating of the transverse heating of the core via the stacktail which would permit a faster rep rate at large stacks.
- AP1 Bunch by Bunch length monitor
  - ☐ Measure effective longitudinal emittance provided by MI so we can identify sources of emittance growth in MI. Reduce bunch length on target will permit for a faster stacking cycle time.

#### **Emittance Control Projects**

- Finish the return ramp from the shot lattice to the stacking lattice.
  - □ Larger stack sizes by about 15%. Faster return to stacking i.e. more stacking time by about ½ hour (3%)
- Bands 2&3 Transverse Core Cooling Equalizers
  - ☐ Increase in Cooling bandwidth by about 0.6 GHz (20%) Lower emittances by 7%
- Build 1-Q Transverse Damper for the Accumulator
  - ☐ Reduce ion instabilities which would permit for smaller transverse emittances during shots to the TEV
- Make Flying Wires in Accumulator Operational
  - ☐ Help monitor Accumulator emittances
- Commission Accumulator Quadrupole Pickup
  - ☐ Will be used to determine beamline match. Will help make pbar emittances in the Main Injector smaller

# Long Term Projects

- In order to support an ultimate luminosity of 400x10<sup>30</sup> cm<sup>-2</sup> sec<sup>-1</sup>, the pbar production rate must climb to 55x10<sup>10</sup> pbars/hr
- The Antiproton Source Department has made significant progress in the following projects (progress should be discussed in break-out sessions)
  - ☐ New Target Optics
    - ➤ 1<sup>st</sup> pass Lattice Design complete
  - ☐ Target Material Study
    - ➤ Inconel 600 study complete
    - ➤ Inconel 625 study in progress
  - ☐ Target Sweeping
    - ➤ Rebuild complete
    - > Pulse testing in progress
    - ➤ Installation during January '03 shutdown
  - ☐ Lithium Lens Upgrade
    - ➤ Assembly process upgrade
      - Chemical processing
      - Pre-load studies
      - DAQ
    - Diffusion Bonded Lens Prototype
      - Prototype #1 to be filled within next month and tested to failure
      - Prototype #2 fabrication in process.

## Long Term Projects (continued)

- □ New trims in the AP2 line
  - ➤ To be installed in January 03 shutdown
- ☐ Moveable Debuncher Quad stands
  - ➤ 10 of thirty fabricated to be installed in January '03 shutdown
- ☐ Debuncher BPM Upgrade
  - ➤ Prototype testing completed.
  - ➤ Full system to be installed in Spring of '03.
- ☐ AP2 Debuncher Aperture Upgrade
  - ➤ Largest single component of future upgrades possible increase in production efficiency 2.3x
  - ➤ Three accelerator physicists are assigned (Gollwitzer, Werkema, Derwent)
  - ➤ Three engineering physicists are assigned (Vander Meulen, Sondgeroth, Budlong)
  - Beam Study plan has been developed.
  - ➤ Collaboration with Technical Division forming.

#### Summary

- Pbar Source is presently supplying enough antiprotons with a sufficient phase space density to support a luminosity in excess of 50x10<sup>30</sup> cm<sup>-2</sup> sec<sup>-1</sup>
- Stacking rate is 66% of the Run II Handbook design goal
  - ☐ Stacking problems have been clearly identified with large momentum spread coming from Debuncher and Stacktail system instabilities
  - ☐ Projects and resources have been identified to increase the stacking rate.
- The groundwork for long-term high luminosity upgrades is proceeding steadily
  - ☐ A significant amount of manpower is being re-focused to long-term projects
  - ☐ These long-term projects are in the initial planning stage.
- Pbar Source Personnel have clearly shown that they are capable of building complicated hardware projects and solving difficult accelerator physics problems.