

- 1) "A" and "B" reset Interlock Box #1.
- 2) "A" and "B" reset Interlock Box #2.
- 3) "A" holds while "B" checks the tunnel spur.
- 4) "A" and "B" reset Interlock Box #3.
- 5) "A" and "B" check the MB grating, the grating door is locked and no one is in the pit.
- 6) "A" and "B" sweep the tunnel to Interlock Box #4.
- 7) "A" holds while "B" checks any cabinets, searches the stub and resets Interlock Box #4. "B" then continues to sweep the tunnel to reset Interlock Box #5.

- 8) "B" joins "A", they enter the hall and "A" holds.
- 9) While "A" holds, "B" sweeps the downstream area and resets Interlock Box #6.
- 10) While "A" holds, "B" checks the MWest area and reset Interlock Box #7.
- 11) Together "A" and "B" sweep the hall going upstream
- 12) "A" holds while "B" checks the upstream area, the grating by the target tube.
- 13) "B" joins "A", they exit and reset Interlock Box #8.

