1) "**A**" and "**B**" enter the MI8 line from the MI8 Service Building.
2) "**A**" and "**B**" travel upstream to Interlock Box #1 and reset it.
3) "**A**" and "**B**" sweep the tunnel to Interlock Box #2. If the mini loop
is made up, they reset Box #2. Else, "**B**" holds while "**A**" checks
the stairwell and resets Box #2A. "**A**" exits the stairwell and resets
Box #2.
4) "**A**" and "**B**" sweep the tunnel to Interlock Box #3. If the mini loop
is made up, they reset Box #3. Else, "**B**" holds while "**A**" checks
the stairwell and resets Box #3A. "**A**" exits the stairwell and resets
Box #3.
5) "**B**" holds while "**A**" sweeps the tunnel to Interlock Box #4. "**A**" Resets
Box #4 and joins "**B**".
6) "**A**" and "**B**" sweep the tunnel to Interlock Box #5. If the mini loop
is made up, they reset Box #5. Else, "**B**" holds while "**A**" checks
the stairwell and resets Box #5A. "**A**" exits the stairwell and resets
Box #5.
'**A**" and "**B**" reset Box #6, and control access out of the MI8 beam line
where they entered.

Reviewed AD/RSO   Date

Michael A Gerardi   4-1-09

Approved AD/OPS Dept. Head   Date

                                         4-2-09