## BNL 200 MeV H<sup>-</sup> Transport and Injection

D. Raparia and Y. Y. Lee

Brookhaven National Laboratory

December 9, 2004

ansport and Injection Mini-Worksh

H- Transport and Injection Mini-Workshop



## OUTLINE


- Introduction
- Transport line
- Injection system
- Beam loss
- Conclusion




# **Acknowledgements**

J. Alessi, K. Brown, YY Lee, K. Zeno,





## **AGS Intensity History**



Brookhaven Science Associates U.S. Department of Energy

BROOKHAVEN
NATIONAL LABORATORY

### **LINAC Beam Parameters**

- Final Energy
- Peak Current
- Repetition Rate
- Pulse Length
- Trans. Emittance(n,rms)
- Energy Spread
- Energy Jitter
- Chopping

- **200 MeV**
- 30-40 mA
- 4 pulses/AGS pulse(7.5 Hz)
- 0.350 ms (250 turns)
- 2 pi mm mrad
- $\pm$  0.1 MeV (0.1 %, 95%)
- $\pm$  0.1 MeV
- Slow + fast

# **BNL 200 MeV Linac**



Br

**U.S. Department of Energy** 

OOKHAVEN
NATIONAL LABORATORY

# **General Parameter of BNL 200 MeV Linac**

Preinjector Energy	0.75	MeV
Output Energy	200.3	MeV
Peak Beam Current	100	mA
Emittance (100mA at 200 MeV)	1	pi cm-mrad
Beam Pulse Length (max)	200	μsec
RF Pulse Length	400	μsec
Operating Frequncy	201.25	MHz
Number of Cavities	9	
Total Length of the Accelerator	144.8	meters
Numbers of unit cells	286	
Total Peak RF Excitation Power	22	MW
Pulse Repetition Rate (max)	10	pulse/sec

Brookhaven Science Associates U.S. Department of Energy


BROOKHAVEN NATIONAL LABORATORY

## **Linac to Booster Transfer Line (LTB)**

- Transport to linac to booster
- Match into booster
- Measure Transverse Beam Quality
- No collimation
- No energy correction
- No buncher cavity
- No chopper in the LTB
- ~ 60 meter long
- 120 degrees bend
- Magnetic stripping of H- not an issue




## **Transfer line layout**






## Lattice function in the transfer line



#### Present mode of operation

#### As design in 1988




Brookhaven Science Associates U.S. Department of Energy


11

BROOKHAVEN NATIONAL LABORATORY


## Diagnostics in the transfer line



## **Losses in the LTB**




#### **Transmission 90-95%**



Current monitor XF011, XF100

**Booster Parameters and Performance** 



### **Booster & AGS Performance**

Imposed limits to lost beam power to maintain hands-on maintenance (ALARA).

■AGS SEB operation, 5.4 s AGS cycle time, 6 Booster cycles.

Achieved 19.6 Tp/sec, Booster Late & 13.7 Tp/second, AGS Late.

Table 1: SEB 10 Pulse Ave. Data (best performance)

\* 1 Tp =  $1x10^{12}$  protons

	Intensity	Efficiency	Beam Loss	ALARA	Loss	Loss/m
	(Tp/cycle)	(%)	(Tp/cycle)	(Tp/cycle)	(kW)	(W/m)
Linac	177					
Liliac	N I I					
Booster Injected	125	71	52	54	0.31	1.5
Booster Extracted	106	86	18	18	0.5	2.5
AGS Injected	78	74	28	31.5	1.62	2.0**
Transition	76	98	2	3	0.26	0.3
After Transition	73	95	3	4.5	0.63	0.8
AGS Late	73	100	0	1.5	0	0

Brookhaven Science Associates U.S. Department of Energy

\*\* assumed lost in AGS



### **Booster & AGS Performance**

Imposed limits to lost beam power to maintain hands-on maintenance (ALARA).

■AGS FEB operation, 2.77 s cycle AGS cycle time, 6 Booster cycles
Achieved 30 Tp/sec, Booster Late & 22 Tp/sec, AGS Late


Table 2: FEB 10 Pulse Ave. Data (best performance, not sustainable operation)

	Intensity (Tp/cycle)	Efficiency (%)	Beam Loss (Tp/cycle)	ALARA (Tp/cycle)	Loss (kW)	Loss/m (W/m)
Linac	115	-	<u>-</u>	<u>-</u>	_	-
Booster Injected	89	77	27	27.7	0.31	1.5
Booster Extracted	83	93	6	9.2	0.33	1.6
AGS Injected	66	78	18	16.3	2.0	2.5**
Before Transition	62.3	94	3.7	1.5	0.9	1.1
After Transition	61.6	99	0.6	2.3	0.2	0.2
AGS Late	61.4	99.5	0.3	0.8	0.25	0.3


\* assumed lost in AGS



## H-Injection




#### Charge exchange foil location Downstream of dipole



# **Bump in the circulating beam at Injection to reduce multiple foil hit**

Brookhaven Science Associates U.S. Department of Energy



#### **Injection in dipole magnet (C5) through yoke**


Foil carbon
Foil thickness 200 μg/cm<sup>2</sup>

No beam dump for H0, H-No stripped electron collector




## **Slow and Fast Bump**

Loc.	Rad
<b>C4</b>	0.00136
<b>C8</b>	0.00039
<b>D1</b>	0.0094
<b>C5</b>	
<b>C3</b>	0.007889
<b>C6</b>	0.002609
<b>C8</b>	0.008153
	C4 C8 D1 C5 C3 C6



## **Painting In H-plane only**

Painting in H-plane only Smoke ring in y-plane




NATIONAL LABORATORY

Brookhaven Science Associates U.S. Department of Energy


## Longitudinal

# Slow chopper in MEBT Fast Chopper in MEBT




Top trace BPM019, Bottom trace current in D1

#### Macropulse Micropulse






# **Line Density from Wall Current monitor**




Line density from wall current monitor.

h=1+2, RF capture at injection. 4 turns per sweep.



RF gap volts sum. 1<sup>st</sup> and 2<sup>nd</sup> harmonic cavities at injection during RF capture.





# **Booster Injection**

- Reducing the risk of a C7 magnet failure
  - Thicker H- stripping foil. Will reduce H<sup>0</sup> to less than 0.3 %
    - 200  $\mu$ gm = 0.4 %
    - 250  $\mu$ gm = 0.09 %
    - Main Issue is emittance growth
  - Add Carbon Block absorber in Quad Upstream of C7, located to catch H<sup>0</sup>
    - Main Issue is does this significantly reduce acceptance?
- Reducing the risk of a C5 magnet failure
  - Restrict acceptance of transfer line, to prevent beam scraping at entrance to C5 (collimation in transfer line)
    - assumes cause is beam scraping at or near the entrance
  - Add Carbon Block between vacuum chamber and coils on inside of C5 magnet, to diffuse and absorb lost particles.

## **C3 Inflector Protection**



Inflector septum distortion. Should be perfectly flat. Presumed cause is high intensity protons scraping on the septum.

## Conclusions

- 1. LTB transport, diagnosis and matches into the booster
- 2. No energy correction, debuncher or collimator
- 3. Transmission 90-95%
- 4. H-plane painting only, Y-plane smoke ring
- 5. Injection efficiency 75-80%